

AHILYNAGAR MUNICIPAL CORPORATION

E-TENDER NOTICE NO.

/2026-2027

Project Department

Ahilyanagar Municipal Corporation invites tender for appointment of private agency for geotechnical investigation at Nalegaon S.no44 (Part) for PMAY 2.0 (AHP) Affordable housing Project.

Sr. n0o	Details of particulars	Start Date &Time	Expiry Date & Time
1	Sale and Preparation of tender	21 /09/2026 17:45	28/09/2026 17:45
2	Submission of Tender	21 /09/2026 17:45	29 /09/2026 17:45
3	Opening of Envelope 1 & 2	30 /09/2026 From 11:00 AM	

Name of Department	Name of Work	Tender Amount (Without GST)	Tender Document Fee (Non Refundable)	E.M.D. (refundable)	Work Period
Project Department	Appointment of private agency for geotechnical investigation at Nalegaon S.no44 (Part) Agarkarmala Ahilyanagar for PMAY 2.0 (AHP)	2,21,221/-	200/-	2100/-	15 Days

Terms and Conditions :

- 1.The tender copy is available for sale in project department, AMC
- 2.It is sole responsibility of the tenderer to purchase and submit tender in mentioned scheduled
3. Conditional tender will not be accepted.
- 4.The commissioner Ahilyanagar Municipal Corporation reserves the right to accept or reject the tenders.
- 5.In case of any dispute arises the Commissioner Ahilyanagar Municipal Corporation decision will final.

Signature of Contractor No.of Corrections Dy.Engineer

6. Tender should be submitted in 3 envelopes, envelope 1 will contain the technical documents. envelope 2 will contain the commercial offer as per annexure A and envelope 1 and 2 will be inserted and sealed in envelope 3
7. The tender published in news paper is also available on the official web site of AMC www.amc.gov.in
8. The tender to be submitted physically in the Project department as per scheduled mentioned in the tender notice


Documents required in envelop 1

1. Document regarding registration of GST
2. Work experience Certificate/work done Certificate
3. Annual turnover of last three years of five lakh (IT Return/Certified from registered CA)
4. Pan Card
5. Undertaking on 500 rupees stamp paper that all the documents submitted in the tender are true and correct and also firm is not blacklisted in any government / semi- government organisation

Mode Of Payment – Part A- Registration Stage

Sr. No	Details of particular	Payment in percentage	Cumulative payment
1	After completion of work ie submission geotechnical investigation report	100 % of approved amount	-


Deputy Engineer


Dy. Commissioner

Ahilyanagar Municipal Corporation

Ahilyanagar Municipal Corporation

ANNUXURE A (On letter of the consultant)

ANNUXURE A

I/We ready to accept the tender for work of appointment of private agency for geotechnical investigation at Nalegaon S.no44 (Part) Agarkarmala Ahilyanagar for PMAY 2.0 AHP project Ahilyanagar Municipal Corporation. The rates for the above work is quoted in percentage as per below

Sr No.	Details of particular	Estimated cost	Rate quoted (above/below)
1	Geotechnical investigation report	2,21,221 (excluding GST)	— Rs Above/below

Seal and sign of the Bidder

Signature of Contractor No.of Corrections Dy.Engineer

Schedule B

Sr.no	Description	Unit	Rate	Quantity	Amount	Amount in words
1	Taking trial bores 75 to 100 mm for 53.0 to 88.9 mm core dia over burden (by diamond drilling machine) such as soil of all sorts, soft murum, hard murum and boulders and in soft rock including all materials such as casing pipes and accessories oil, grease, steel, rods, and such other materials as required (including conveying the material to site of work) . Preserving the loose sample in glass jar and core sample serially on site of work and conveying the same to HQ of concernring office as directed. R.A.for 10.00 Rmt a) over burden 0 to 50 meter. DSR P/1- 21/1.45	Rmt	2110	40	84400	Eighty four thousand four hundred
2	Taking trial bores 75 to 100 mm for 53.0 to 88.9 mm core dia in rocks as specified below including all necessary materials such as oil,grease,steel boostan and such other materials as required (including conveying the material to site of work) and Preserving the core sample core sample serially on site of work and conveying the same to HQ of concernring office as directed. Quartzite with diamond drill with Ax Bit 0 to 50 metre DSR P/I- 22/1.48	Rmt	3910	0	0	Nil
3	Providing tun tappa core boxes of jungle wood of size1.25mx 0.35% 0.15m for preserving core sample with all fixtures and fastening handles including locking arrangment etc . complete. DSR P/I- 22/1.49	Nos	5665	4	22660	Twenty two thousand six hundred and sixty
4	Conveying the boring machine and engine and all its accessories etc. to the site of the work and back including loading unloading etc. complete. Rate mechanical (Note Distance to be measured from the station of boring machine engine etc. of district head quarters to site of the work by short route). DSR P/I- 23/1.54	KM	68	140	9520	Nine thousand five hundred and twenty
5	Shifting boring plant with all its components and reinstalling the same at the directed place including all its charges etc. complete.	Nos	9067	3	27201	Twenty seven thousand two hundred and

6	Providing detailed reports of the inspection logging of drilled hole by observing visual description of data as per depth, thickness of layer, type of sample, wash sample, bore recovery type of drill etc. complete. DSR P/I- 23/1.56	Nos	9680	4	38720	Thirty eight thousand seven hundred and twenty
7	Providing detailed geological reports of proposed site by maintaining geotechnical investigation of structure stratification collecting soil, rock and ground water samples for laboratory tests to arrive the foundation design parameters . Rock properties such as type of rock, jointing fractures, etc. complete with suggestion about the site foundation and remedies. DSR P/I- 23/1.57	Report	38720	1	38720	Thirty eight thousand seven hundred and twenty
8	Providing and maintaining temporary platform for erecting boring machined in river bed to the depth of standing water 2 m and above and of size 3.50 x 4.00 M by using 20 Nos. of M.S. empty barrels in M.S. frame made of M.S. angle size 50 x 50 x 5 mm with abrication and over it a jungle wood planks platform of size 3.50 x 4.00 x 0.03 M size including supplying of nylon rope 24 mm dia. for anchoring platform include passage platform and enganging a labour etc. complete. 2 m and Above.	Nos	21810	0	0	NII


Deputy Engineer
Project Department
Ahliyanagar Municipal Corporation